8701 Support brackets to bridge deck

REVISION 05/04/13

8701.1 General

This supplementary specification refers to the supply and installation of conduit support brackets to the bridge deck.

8701.2 Referenced Documents

This supplementary specification shall be read in conjunction with the following:

- MRS01 *"Introduction to Specifications"*;
- MRTS01 *"Introduction to Technical Specifications"*;
- MRS77 *"Bridge Deck"*;
- MRTS77 *"Bridge Deck"*; and
- the project Drawings.

8701.3 Description of Works

The following work items are covered by this supplementary specification:

Task Item No.	Description	Unit of Measurement
8701	Supply and installation of support bracket for [conduit] to bridge deck (Refer Supp Spec No. 8701)	lump sum

8701.4 Work Operations

Work operations incorporated in this item will include:

a) Work operations included in Clause 2.1.5 on MRS01 "Introduction to Standard Specifications";
b) Supply and delivery to site of all galvanised steel support;
c) Supply and delivery to site of all required fixings and rubber supports; and
d) Installation of support brackets to side of bridge deck.

8701.5 Measurement and Payment

Payment for these works shall be deemed to be included in the scheduled unit rate for the item(s) shown in Clause 8701.3 of this supplementary specification.