

Supplementary Specification

MRC Supplementary Specification

8204 Hand Placed Fibre Reinforced Concrete Paving

Revision 3.0

January 2026



Contents

8204.1	Introduction	4
8204.1.1	Definitions of Terms.....	4
8204.2	Referenced Documents	4
8204.3	Description of Work Items.....	5
8204.4	Quality Systems Requirements.....	5
8204.4.1	Std Test Methods (Testing Regime).....	5
8204.4.2	Hold Points, Witness Points and Milestones	5
8204.4.3	Construction Tolerances	7
8204.5	Preliminary.....	7
8204.5.1	Materials	8
8204.5.1.1	Concrete Specification	8
8204.5.1.2	Fibre Reinforcing Specification	8
8204.5.1.3	Mixing and Placing Concrete	9
8204.5.2	Contractors Personnel	9
8204.5.3	General Workplace Health and Safety Requirements.....	9
8204.5.3.1	Council Work Health Safety Contractor Requirements.....	9
8204.5.3.2	Safe Systems of Work / Risk Assessment	10
8204.5.4	Legislative Compliance.....	10
8204.5.5	Permits for Work.....	10
8204.6	Construction	10
8204.6.1	Work Operations.....	10
8204.6.1.1	Work Scope.....	11
8204.6.2	Supply of all Materials.	11
8204.6.3	Site layout with Superintendent.....	11
8204.6.4	Preparation of Base/Floor.....	11
8204.6.4.1	Carrying out Excavations/Embankment Works (as required)	11
8204.6.5	Preparation of Foundation Bedding (as required).....	12
8204.6.6.1	Installation of Formwork	12
8204.6.6.2	Installation of Reinforcing and Joints (as required).....	12
8204.6.6.3	Placing Compressible Packing;.....	13
8204.6.7	Placing, Finishing, and Curing Concrete.....	13
8204.6.7.1	Placing and Compacting Concrete;.....	13
8204.6.7.2	Finishing and Curing Concrete	14
8204.6.7.3	Stripping of Formwork	14



8204.6.8	Clean Up and Backfilling Against Footing and/or Slab.....	14
8204.6.9	Acceptance and Rejection of Concrete.....	14
8204.6.9.1	Rejection of Concrete (Plastic – Non Hardened)	14
8204.6.9.2	Rejection of Concrete (Hardened)	14
8204.6.9.3	Acceptance of Concrete.....	14
8204.6.9.4	Defects and Rectification	15
8204.7.1	Collection and Submission of All As Constructed Data.....	15
8204.7.2	Erosion and sediment control plan.....	15
8204.8	Measurement and Payment	15



8204.1 Introduction

This supplementary specification refers to the supply and placement of polymer fibre reinforced concrete paving. Its use shall be limited to cast insitu (non-structural) elements, shotcrete or precast concrete elements (steel fibres are not permitted to be used in the concrete mix).

8204.1.1 Definitions of Terms

This section describes any term which are specific to this specification or requires clarification due to an ambiguous understanding.

Term	Definition
Fibre Reinforced Concrete	A composite material consisting of conventional concrete mixed with uniformly distributed, discrete fibres that enhance the concrete's mechanical properties. For the purposes of this specification to only refer to polymer fibres.
Macro Synthetic Fibre	Fibres imparting significant post-cracking capacity to concrete, used as a replacement for steel reinforcement. Macro fibres are typically 40–65 mm long and 0.3-1 mm wide.
Micro Synthetic Fibre	Fibres that create a support network within the concrete which increases its tensile strain capacity for control of plastic shrinkage cracking, but do not offer concrete post-cracking load capacity. Micro fibres are typically 12-51 mm long and < 0.3 mm wide.

8204.2 Referenced Documents

This supplementary specification shall be read in conjunction with the following:

- MRS01 *"Introduction to Specifications"*;
- MRTS01 *"Introduction to Technical Specifications"*;
- MRS03 and MRTS03 *"Drainage Structures, Retaining Structures and Embankment Slope Protections"*; applicable to shotcrete works;
- NRS04 and MRTS04 *"General Earthworks"*;
- MRS50 and MRTS50 *"Specific Quality System Requirements"*;
- MRS70 and MRTS70 *"Concrete"*;
- MRS72 and MRTS72 *"Manufacture of Precast Concrete Elements"*;
- MRTS272 *"Shotcrete for Aboveground Application"*
- MRTS273 *"Fibre-reinforced Concrete"*;
- AS 1379 *"Specification and Supply of Concrete"*;
- ASTM C 1116/C116M *"Standard Specification for Fiber-Reinforced Concrete"*;
- I.S. EN 14889-2 – *"Part 2 Polymer Fibres – Definitions, Specifications, and Conformity"*; and
- the project Drawings.



8204.3 Description of Work Items

Work items incorporated by this supplementary specification are identified in Section 8204.6 and 8204.7 with individual activities/tasks for measurement and payment sourced from the Bill of Quantities and listed in MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving Section 1

8204.4 Quality Systems Requirements

8204.4.1 Std Test Methods (Testing Regime)

Unless otherwise approved by the Superintendent the following minimum testing regime applies to this specification:

The minimum test frequencies and minimum numbers of tests shall be as follows:

- Concrete shall be tested in accordance with MRTS273 Fibre Reinforced Concrete.
- Earthworks shall be tested in accordance with MRTS04 General Earthworks.

Survey requirements of the concrete paving shall be surveyed to ensure compliance with the design drawings.

Where there are additional testing requirements these are included in Clause 2 of MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving

8204.4.2 Hold Points, Witness Points and Milestones

Milestone

Milestone is a point within a project which marks the start or completion of an activity or compliance requirement. Generally associated with provision of records or data for verification with the projects contract and specification.

Hold Points

Hold points are noted on various Sections of this Specification.

“HOLD POINTS” are critical stages of the work, which require inspection by the Superintendent (or his nominated representative) and beyond which the Contractor will not be permitted to proceed without the written approval of the Superintendent.

A written “request for inspection” form shall be submitted to the Superintendent at least 48 hours prior to reaching the relevant “HOLD POINT”. One copy shall be submitted for each inspection. The signed copy will be handed back to the Contractor after the inspection to sanction work to proceed to the next stage or noting what work has to be done prior to re-inspection. This may involve inspection of the works by the Superintendent or approval of test results forwarded to the Superintendent by the Contractor.

Witness Points

Witness Points are also important stages of work. However, these are not necessarily as critical work stages as defined by the hold points. Witness points are where the Superintendent (or his/her nominated representative) may review, witness, and inspect the work. The activities however may continue to proceed.



The following table represents the minimum inspection and milestone requirements for this specification;

Activity	Inspection Type	When	Reference
Construction Procedure and other required documents as per 8210.5	Milestone	4 Weeks prior to works commencing	8204.5
Concrete Mix Design	Milestone	14 days prior to placing order for concrete	8204.5
Inspection of delivered items	Hold Point	At delivery time for each item.	8204.6.2
Final location of work extents	Hold Point	Prior to excavation commencing	8204.6.3
Unsuitable material at excavated floor	Hold Point	Prior to trimming and compacting for floor	8204.6.4.1
Floor compaction and inspection	Hold Point	Prior to formwork and concrete pour setup commencing	8204.6.4.2
Preparation of foundation bedding to design drawings	Hold Point	After compaction and trimming of foundation bedding to design drawings	8204.6.5
Laying of polythene sheeting	Witness Point	Prior to setting up formwork	8204.6.5
Pre-pour survey of formwork	Hold Point	Prior to concrete pour approval to proceed	8204.6.6.1
Set up of reinforcing and joints	Witness Point	Prior to concrete pour approval to proceed	8204.6.6.2
Placing of compressible packing	Witness Point	Prior to concrete pour approval to proceed	8204.6.6.3
Approval to carry out concrete pour	Hold Point	After pre-pour inspection has been carried out	8204.6.7.1
Concrete pour process and procedure being followed	Witness Point	During concrete pour	8204.6.7.1
Joints installed as per design drawings and sealed	Witness Point	After formwork is removed	8204.6.7.1
Finish of concrete as per design drawings	Witness Point	Prior to concrete hardening	8204.6.7.2
Curing of concrete to occur immediately after pouring	Witness Point	Immediately after pouring for 7 days	8204.6.7.2
Stripping of formwork approval	Hold Point	No earlier than 72 hours after concrete pour finish, approval by Superintendent	8204.6.7.3



Activity	Inspection Type	When	Reference
Backfilling against concrete including clean up of site	Witness Point	After approval to remove formwork being granted by Superintendent	8204.6.8
Rejection of “plastic” concrete	Hold Point	During pouring of concrete	8204.6.9.1
Rejection of hardened concrete	Hold Point	After test compressive test results have been submitted	8204.6.9.2
Acceptance of concrete workability and consistency	Witness Point	During pouring of concrete, process followed	8204.6.9.3
Concrete compressive strength acceptance	Hold Point	Acceptance of test results	8204.6.9.4
Rectification of defects	Hold Point	After setting and curing, and during “On Maintenance” period	8204.6.9.5
Works as executed documentation submitted and accepted	Hold Point	4 weeks prior to Works as Executed inspection request	8204.7.1
Erosion and sediment control measures in place	Hold Point	At completion at Works as Executed Inspection	8204.7.2

8204.4.3 Construction Tolerances

Unless otherwise approved by the Superintendent the following construction tolerances shall apply to this Supplementary Specification;

The construction activity outcome shall not depart from the widths, lengths, heights, and shapes specified by the relevant specifications as applies to this specification;

- Concrete tolerances in accordance with MRTS70 Concrete;
- Earthworks tolerances in accordance with MRTS04 General Earthworks;
- Unbound Gravel tolerances in accordance with MRTS05 Unbound Pavements;
- Shotcrete tolerances in accordance with MRTS03 and MRTS272.

Tolerances specific to the project are detailed on the design drawings and are included in Clause 2 of MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving.

8204.5 Preliminary

The project design manager shall ensure that the required State government permits have been obtained and are current prior to the issuing of tender documents.

The Contractor is to submit the following documentation 4 weeks prior to commencing work or a prestart is conducted:

- Works procedure – all activities and order of construction;
- Quality Plan;
- Contractor’s personnel experience;



- Work Health & Safety Plan;
- Environmental Management Plan;
- Concrete mix design – 14 days prior to placing order for concrete.

Other preliminary requirements unique to the project will be listed in the MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving.

MILESTONE

The contractor is to ensure their construction activities are based on the design drawing requirements.

8204.5.1 Materials

Supply of all materials to site is the responsibility of the Contractor at their cost, where items are Principal supplied the nominated storage site shall be obtained from MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving Section 3 and shall be the point of supply.

All items and materials shall be supplied in accordance with the design drawings and the relevant specification/s MRTS03, MRTS04, MRTS70, MRTS272, and other standards as referenced.

Polythene sheeting shall be supplied and placed in accordance with requirements of Clause 15.6 of MRTS70.

8204.5.1.1 Concrete Specification

The compressive strength of the concrete and the concentration of the fibre reinforcing to be used shall be in accordance with requirements of MRTS70, and as specified on the project Drawings.

8204.5.1.2 Fibre Reinforcing Specification

Fibre reinforcing materials for use in this application shall have the following material properties and shall comply to the requirements of *ASTM C 1116/C116M "Standard Specification for Fiber-Reinforced Concrete"* and I.S. EN 14889-2 – *"Part 2 Polymer Fibres – Definitions, Specifications, and Conformity"*.

Property	Macro Fibres	Micro Fibres
Material: polypropylene	100% Polyolefin Polymer	Virgin
Length	48 mm	19 mm
Equivalent / nominal diameter	0.71 mm	35 µm
Melting point	170°C	150°C - 170°C
E modulus	6.9 GPa	3.5 GPa
Density	0.92 g/ml	0.91 g/ml
Tensile strength	550+ MPa	450 - 560 MPa
Energy absorption rate	450+ Joules	Not applicable
Fibre type	Continually embossed	Mono filament
Absorption	Nil	Nil
Alkali, acid and salt resistance	High	High
Thermal conductivity	Low	Low



Electrical conductivity	Low	Low
Fibres per kg	32,000	

8204.5.1.3 Mixing and Placing Concrete

Mixing and placement of the fibre reinforcing shall be executed in accordance with the following requirements:

1. Add fibre reinforcing as flexural and/or secondary reinforcement to concrete mixture in accordance with manufacturer's specifications before, during or after loading other concrete materials.
2. Add the synthetic fibre reinforcement at standard application rates as specified for the required dosage rate as indicated in the Project Drawings.
3. Mix for a minimum of three (3) minutes with full speed for uniform distribution of fibre through the concrete matrix.
4. Place, finish and cure concrete in accordance with manufacturer's instructions, MRTS70, MRTS03, MRTS272, MRTS273.

The concrete batching contractor shall submit their concrete mix design and mixing procedure 14 days prior to delivery to site

MILESTONE

8204.5.2 Contractors Personnel

Personnel, sub-contractors and suppliers utilised in the preparation of the base, laying of the pavers, and their sealing shall be experience in the processes and activities required to carry out the works.

The Contractor shall provide documented evidence for the Superintendent's approval to demonstrate the experience, qualification, skills and training of proposed personnel, sub-contractors a minimum 4 weeks prior to works commencing.

MILESTONE

8204.5.3 General Workplace Health and Safety Requirements

As a condition of this document, it is required that the Contractor and its workers (including all sub-contractors etc., and their workers) engaged to perform a service or work on site must at all times ensure (so far as reasonably practicable) the health and safety of all persons who are, or may be, affected by work under this Supplementary Specification or the services provided.

8204.5.3.1 Council Work Health Safety Contractor Requirements

As a minimum, the Contractor must ensure they and their workers (including all Contractor's sub-contractors etc.) comply with the following work health and safety requirements:

- Undertake Council Contractor and site inductions prior to commencing work.
- Ensure all workers are competent, and provide proof of competencies, licenses, and training on request.
- Have an approved safe system of work (including risk assessment) for the task and ensure the work is completed according to this safe system of work.
- Provide adequate supervision for all high-risk construction tasks.
- All incidents and near misses are to be reported to their Council representative within 60 minutes.
- Participate in Contractor pre-start meetings, safety interactions, site meetings and site inspections.



- Review information provided by Council such as site-specific hazards, risks and interaction issues and implement controls to, so far as reasonably practicable, eliminate, or if that is not possible, mitigate the risk.
- Supply safe plant and equipment with pre-start checks, maintenance/ service records and manufacturer's manual.
- For all hazardous chemicals, ensure current Safety Data Sheets (SDS) are available and that appropriate controls (including as required under SDS requirements) are implemented.
- Comply with Council Safety, Drug and Alcohol and Fitness for Work policies.
- Be familiar with applicable site emergency procedures, closest emergency assembly point and sign in and out of site registers where required.
- Compliance with any reasonable direction given by Council relating to work health and safety.

8204.5.3.2 Safe Systems of Work / Risk Assessment

The Contractor must prepare and submit a safe method of work (risk assessment) and relevant controls prior to commencement of work.

The completed risk assessment is to be provided to the Superintendent for review and approval prior to works commencing. Safe Work Method Statements (SWMS) are required for all high-risk construction activities (e.g. entry and work within manholes) and Job Safety Analysis (JSA) or similar risk assessments are required for other tasks. The risk assessment (whether SWMS, JSA or other) must be reviewed and signed by the workers prior to undertaking the work.

MILESTONE

The Contractor shall implement a Safety Management System (SMS) that includes sections addressing the project scope.

8204.5.4 Legislative Compliance

Without limiting the Contractor's other obligations, the Contractor must comply with all Acts, Regulations, Standards and Codes of Practice about work health and safety matters that are applicable to the scope of work undertaken or services being provided.

8204.5.5 Permits for Work

The Contractor must ensure applicable permits for the various work activities are completed and approval issued by the statutory body for those works, all requirements for submission, completion, and obtaining permits shall be at the Contractors cost.

8204.6 Construction

Carry out all works associated with the supply and placement of the fibre reinforced concrete as specified on project drawings.

This section lays out the works operations with more detail based on specific requirements of this supplementary specification. Some activities may appear to include items which are stated within other specifications, the purpose is to reinforce that requirement specific to this supplementary specification.

Specific construction requirements associated with these works is detailed in MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving, Section 5.

8204.6.1 Work Operations

Work operations incorporated in this item are those included in Clause 2.1.5 of MRS01 "Introduction to Standard Specifications" and the following work scope activities and associated sub activities;



8204.6.1.1 Work Scope

The scope of works (including all associated sub activities) covered under this specification is as follows:

- Procure, supply, and store all materials as required;
- Site layout marking;
- Carry out earthworks for preparation of foundation for paving;
- Carry out bedding works to prepare for pouring of concrete;
- Installation of formwork, reinforcing (as required), and joint set up (including fibre installation);
- Placing, finishing, and curing of concrete;
- Backfilling against concrete and clean-up of site;
- Survey conformance of finished surface levels; and
- Collate and submit "As Constructed details.

8204.6.2 Supply of all Materials.

All materials, plant, and labour required to carry out the works under this Specification is to be supplied by the Contractor, where materials are Principal supplied the designated storage site will be the point of supply for the purposes of this Specification.

All items shall be inspected at delivery to site prior to use. Any items which are damaged are not to be used and are to be returned to the supplier.

HOLD POINT

8204.6.3 Site layout with Superintendent

The final location of the works as required by the design drawings is to be marked out on site and shall be inspected and approved by the Superintendent prior to excavation commencing.

HOLD POINT

8204.6.4 Preparation of Base/Floor

The Contractor shall carry works to prepare the base for the paving to be sited/poured on, this may include excavation and/or embankment works as required by the design drawings. All works shall be carried out in compliance with MRTS04.

8204.6.4.1 Carrying out Excavations/Embankment Works (as required)

The Contractor shall carry out earthworks to level and grade as required by the design drawings and MRC Standard Drawing A2-00500 in compliance with MRTS04 and the Contractors Works Procedure, finished surface levels shall have a vertical tolerance not exceeding +5mm/-10mm. The finished surface is to be inspected for areas of unsuitable material.

HOLD POINT

If unsuitable material is identified this is to be removed and replaced with approved material as per the instructions of the Superintendent.

8204.6.4.2 Finished Floor or Surface (Earthworks)

All loose material is to be removed from the finished floor or surface.

Compact the floor or surface as required by the design drawings and MRTS04, where there is a lack of detail the area shall be compacted to 97% SDD and tested at a frequency of 1/200m²

Floor or surface preparation is to comply with the design drawings and MRTS04 and is to be presented for inspection by the Superintendent with inspections, geotechnical testing and survey requirements applying



unless otherwise stated within this Specification or in MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving.

HOLD POINT**8204.6.4.3 Utilising or Disposing of Excavated Material;**

Excess excavated materials shall be disposed of by the contractor or utilised as per Superintendents instructions. Material stockpiled shall ensure that all Environmental ESC measures are in place and maintained.

8204.6.5 Preparation of Foundation Bedding (as required)

The Contractor shall prepare, lay, compact, and finish the foundation bedding layer as required by the design drawings and MRC Standard Drawing A2-00500, including thickening at control and expansion joints. Where type 2.4 gravel is laid the Contractor shall comply with MRTS05 for all requirements unless otherwise stated within this Specification or in MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving.

Prior to setting up formwork the bedding is to be presented for inspection by the Superintendent with inspections, geotechnical testing and survey requirements applying unless otherwise stated within this Specification or in MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving.

HOLD POINT

Where the concrete is to be placed on the ground surface or foundation bedding a Polythene Sheeting is to be laid in accordance with MRTS03 and MRTS70.

WITNESS POINT**8204.6.6 Installation of Formwork and Reinforcing (as required)**

Upon approval to proceed and the laying of polythene sheeting the Contractor shall carry out setting up of formwork and any primary reinforcing and joints installation required.

8204.6.6.1 Installation of Formwork

Formwork to be used has been approved by Superintendent and complies with MRTS70.

Installed formwork shall be installed to project drawings line, levels and shape, positional tolerance Horizontal +/-25mm's, Vertical +/-5mm's

Depth from foundation bedding to design finished level must comply with project drawings design depth of concrete, acceptable tolerance +10/-3mm's shall not be exceeded.

HOLD POINT**8204.6.6.2 Installation of Reinforcing and Joints (as required)**

The Contractor shall ensure all reinforcing requirements and joints are to comply with the design drawings, where there is a lack of detail joints shall be installed as per MRTS70.

Control and Expansion joints shall be installed when the formwork installation is complete and shall be 'Danley Key Joint' and 'Danley PaveX Expanda HD' proprietary products or similar approved equivalent products in the locations and joint type as required by the design drawings.

Primary reinforcing in the case of shotcrete concrete shall be installed as required by the design drawings.

WITNESS POINT



8204.6.6.3 Placing Compressible Packing;

Where indicated on the design drawings compressible packing shall be installed prior to placement of the concrete. Where there is a lack of detail compressible packing shall be installed as per MRTS70 or as required by design drawings and/or MRC Standard Drawings.

WITNESS POINT

8204.6.7 Placing, Finishing, and Curing Concrete

Upon approval to carry out the concrete pour the Contractor shall place, compact, cure, and strip formwork as required by this specification, MRTS273, and MRTS70. All dimensions and surface finish requirements shall be as per the design drawings.

The Contractor shall ensure quality of the concrete meets with the requirements of this specification, where concrete does not meet the specification requirements the Superintendent shall reject any non-conforming concrete while in its plastic state before setting and hardening, refer to Clause 8204.6.9.

Prior to commencement of the pour the Contractor shall check all dimensions are correct, and installed joints and compressible packing are in place as required by the design drawings.

8204.6.7.1 Placing and Compacting Concrete;

Prior to approval for placing the concrete a pre-pour inspection of formwork and joints is to be carried out, all joints and dowels linking to adjacent section pours are to be installed as per the design drawings prior to the respective pours taking place. The Superintendent shall give approval to proceed with the respective pours.

HOLD POINT

All concrete works (including formwork and reinforcing) associated with the Fibre reinforced concrete shall comply with the design drawings and be carried out in accordance with MRTS70 and MRTS373, with inspections, geotechnical testing and survey requirements applying unless otherwise in MRC Supplementary Specification Annexure 8204_1 Hand Placed Fibre Reinforced Concrete Paving.

WITNESS POINT

Concrete delivered to site is as per the approved mix design, delivery dockets verifying mix and target strength.

Concrete is to be placed with minimum drop height to minimise segregation. Compaction of concrete shall occur using a vibrating needle, with insertion directly perpendicular (up and down) to the finished surface and not more than 450mm apart for between 5-15 seconds at each location. No dragging of needle along surface is permitted. Care should be taken to ensure the fibres are not segregated from the concrete mix during compaction.

Vibrating against steel reinforcing should be avoided, no vibrating of formwork or tapping/hammering of formwork is to occur.

Depressions in the fresh concrete caused by foot traffic, or aluminium screeding tools, must be refilled with the concrete mix, not just surface slurry.

Care shall be taken to avoid uneven screeding that will cause 'screed-lines' of mortar and /or aggregate to become apparent when the surface has been washed. Over-screeding by an overlapping technique has been found to be an effective method to avoid this finishing problem.

Use placing methods that minimise plastic cracking. Closing plastic cracking by merely trowelling is not sufficient, as they will again be revealed after washing. If plastic cracking occurs during placement, they shall be closed by careful and efficient surface compaction before re-trowelling.



Construction and Contraction/Expansion Joints are to be incorporated as per the project plans or as per the Superintendents instructions.

WITNESS POINT

8204.6.7.2 Finishing and Curing Concrete

Finishing of the concrete is to be in accordance with the design drawings.

WITNESS POINT

Immediately after the initial set of the concrete, curing shall commence and continue for a minimum of seven (7) days. Plastic sheeting shall not be used as part of the curing process.

WITNESS POINT

8204.6.7.3 Stripping of Formwork

Formwork is not to be stripped for 72 hours and loading not to occur for seven (7) days or as per design drawings and approved by the Superintendent.

HOLD POINT

8204.6.8 Clean Up and Backfilling Against Footing and/or Slab

Backfilling to slab is not to occur until after stripping has occurred. Where backfilling and turfing is required, it shall be left 10mm below level of concrete finished surface level. Site is to be cleaned of all debris, excavated material, and construction materials.

HOLD POINT

8204.6.9 Acceptance and Rejection of Concrete

The Superintendent shall make the Contractor aware of the following acceptance or rejection criteria for the placed concrete.

8204.6.9.1 Rejection of Concrete (Plastic – Non Hardened)

Prior to concrete being placed it shall be visually checked and be rejected if the following apply

- a) The slump is outside the limits and tolerances specified on the project plans and/or MRTS273.
- b) The concrete contains significant lumps of unmixed material.
- c) Appearance, colour, cohesiveness is significantly different to other batches delivered and placed.

HOLD POINT

8204.6.9.2 Rejection of Concrete (Hardened)

Concrete may be rejected based on strength as per MRTS70.

HOLD POINT

8204.6.9.3 Acceptance of Concrete

During the placing stage the consistency and workability of concrete shall be such that it can be handled and transported without segregation and can be placed, worked and compacted into all corners, angles and narrow sections of forms during the placing stage.

WITNESS POINT



The strength of the concrete passes all compression tests and all test results are within the parameters of rejecting as laid out in MRTS70 and the requirements of Clause 11 of MRTS273.

HOLD POINT

8204.6.9.4 Defects and Rectification

Where concrete does not comply with this specification the concrete shall be removed and replaced.

Where cracking has occurred including during the “On maintenance” period rectification will be dependent on the size, type, and extent of cracking, and the cause. Any rectification method will be as per approval of the Superintendent.

HOLD POINT

8204.7 Post Construction

Items which close out the project, and readies the project for the “On Maintenance” inspection. All items below **MUST** be complied with prior to the Contractor requesting an “On Maintenance” inspection.

8204.7.1 Collection and Submission of All As Constructed Data.

Contractor is to supply and submit Works as Executed documentation as required by *MRC D20 - Drawings and Documentation* for approval by the Superintendent 4 weeks prior to requesting a practical completion inspection.

HOLD POINT

Format of submitted “As Constructed” documentation shall be compliant with MRC Supplementary Specification 8919.

8204.7.2 Erosion and sediment control plan

ESC measures are to be kept in place and maintained until the Superintendent approves of the removal of such measures.

HOLD POINT

8204.8 Measurement and Payment

No separate payment will be made for the works specified in this Supplementary Specification or it’s Annexure. Provision for these works shall be deemed to be included in the scheduled unit rates for the items shown at Clause 8204.3. The calculation of these quantities shall be in accordance with Clause 2.3 of MRS70.

Version Control:

Version	Description	Reviewed / Endorsed	Date
1.0	Original issue		01.02.2016
1.1	Review	R. Mogg	07.04.2022
2.0	Review of specification	C. Sultana	07.02.2024
3.0	Full Review of Specification	C. Sultana	29.01.2026